## **III. ERECTION NOTES:**

- **III(a).** "VERTARIB" PANELS ARE SIDING PANELS ONLY AND ARE NOT TO BE INSTALLED IN A ROOFING APPLICATION.
  - III(b). SIDE LAP FASTENERS TO BE SPACED 16" O/C MAX.
- **III(c).** CLOSED CELL POLYETHYLENE CLOSURES FACTORY FORMED TO THE PANEL PROFILE TO BE FIELD INSTALLED WHERE NECESSARY TO WEATHERTIGHT THE PANEL SYSTEM.
- **III(d).** "VERTARIB" PANELS ARE TO BE SQUARE WITH BUILDING & ALIGNED USING MARKS @ THE EAVES & BASE. MARKS TO BE 36" ON CENTER
- **III(e).** ANY CUTTING OR BEVELING OF PANELS @ ENDS OF PANEL RUNS OR PENETRATIONS TO BE DONE BY THE ERECTOR IN THE FIELD.
  - III(f). REMOVE ALL STRIPPABLE PLASTIC AS PANELS ARE BEING ERECTED.

## **IV. CLEAN-UP NOTES:**

- **IV(a)** INSPECT ENTIRE SIDING AREA. REMOVE ANY PIECES OF STRIPPABLE PLASTIC FILM STILL LEFT ON PANELS OR FLASHING. MAKE SURE FLASHING IS PROPERLY INSTALLED AND CAULKED WHERE SHOWN ON DETAILS.
- **IV(b).** ANY METAL SHAVINGS FROM FIELD CUTTING OR DRILLING OF PANELS MUST BE CLEANED OFF SIDING EACH DAY TO PREVENT RUST AND/OR DISCOLORATION OF PANELS.
- **IV(c).** TOUCH-UP ANY SCRATCHES, NICKS, OR FASTENER HEADS WITH TOUCH-UP PAINT. MAKE SURE AREA IS THOROUGHLY CLEANED AND USE ONLY AN ARTISTS BRUSH. COVER ONLY THE SCRATCH DO NOT PAINT OVER ANY PREPAINTED AREA.

## V. CAUTIONS:

- V(a). CARE MUST BE TAKEN TO NOT OVER TORQUE FASTENERS.
- **V(b).** CARE MUST BE TAKEN IN PROTECTING SIDING PANELS FROM OTHER TRADES, DISSIMILAR METALS, AND POSSIBLE RUN OFF OF HVAC EQUIPMENT.
- **V(b1).** CARE MUST BE TAKEN NOT TO STEP ON PANEL BETWEEN FIRST PURLIN AND EAVE WHEN FASTENING EAVE SCREWS. THIS MAY CAUSE PONDING OF WATER.
- **V(c).** THE DETAILS CONTAINED IN THE FOLLOWING PAGES ARE MERELY RECOMMENDATIONS AS TO HOW "FLEXOSPAN, INC." MATERIALS SHOULD BE INSTALLED. THEY MAY REQUIRE ADAPTATIONS OR MODIFICATIONS FOR A SPECIFIC PROJECT AS CONDITIONS VARY IN BOTH BUILDING DESIGN AND LOCAL WEATHER PECULIARITIES.
- V(d). THESE STANDARD DETAILS ARE PROVIDED FOR REFERENCE ONLY. OTHER DETAILS MAY BE NECESSARY BASED ON ACTUAL JOBSITE CONDITIONS, BUILDING CODE AND REGULATORY ISSUES, OWNER/ARCHITECT/CONTRACTOR/ERECTOR REQUIREMENTS AND MANY OTHER FACTORS. THE PURCHASER IS RESPONSIBLE FOR THE SELECTION, USE AND IMPLEMENTATION OF THE PROPER DETAILS.
- **V(e).** INSURING WATER-TIGHTNESS ON ANY GIVEN PROJECT IS THE FUNCTION OF THE INSTALLER. THE ARCHITECT/GENERAL CONTRACTOR/INSTALLER HAVE THE RESPONSIBILITY TO SELECT DETAILS TO INSURE ADEQUATE WATER-TIGHTNESS TO MEET PARTICULAR BUILDING REQUIREMENTS.

$\sim\sim\sim\sim\sim\sim$
FLEXOSPAN
***************************************
BOX 515 RAILROAD STREET

SANDY LAKE, PENNSYLVANIA 16145-0515

PHONE: 800-245-0396 ° FAX: 724-376-3864

"Vertarib" Standard
Details

General Notes(cont.)

DRAWN BY: D.UREY DATE:9/26/05 DRAWING NO.

CHECKED BY: DATE:

/ertarib-2