


## INSTALLATION SEQUENCE

- 1. ADHERE CHANNEL ISOLATORS TO (OPTIONAL) SLEEPERS
- $\hbox{2. SPACE CHANNEL ASSEMBLY PER CONSTRUCTION DRAWINGS/GUIDELINES}\\$
- 3. PLACE LOW DENSITY ACOUSTICAL ABSORPTION MATERIAL (OPTIONAL).
- 4. INSTALL FIRST LAYER OF PLYWOOD ACROSS CHANNELS OR SLEEPERS AND SCREW IN PLACE. BE SURE TO STAGGER SEAMS
- 5. COVER WITH (OPTIONAL) BUILDERS FELT AND / OR TROWELED WOOD ADHESIVE.
- 6. INSTALL SECOND LAYER OF PLYWOOD, CROSS LAPPING THE FIRST LAYER AND SCREW IN PLACE.
- 7. APPLY FINISH FLOOR PER MANUFACTURER



DIMENSION FORMAT: IN (mm)

MOISE CONTROL

TITLE MODEL FC
WITH WOOD FLOOR
INSTALLATION SEQUENCE

LAST DATE REVISED 9/2/08

drawn by MDV drawing no. AAOO1824

ΑА

<sup>\*</sup> TO REDUCE SQUEAKING BETWEEN PLYWOOD LAYERS