

ERECTOR NOTES:

- 1. IF "FSS-1.5" ROOF PANEL DOES NOT END ON A HIGH RIB THEN THE PANEL MUST BE FIELD SLIT ALLOWING FOR 1 1/4" TO BE BENT INTO A VERTICAL LEG AND USED IN CONJUNCTION WITH THE SEALER TAPE, & POP RIVETS.
- 2. START GABLE TRIM @ EAVE & PROCEED UPWARDS CAULKING AND LAPPING EACH 4" MIN.
- 3. VERTICAL LEG OF "FSS15-02" GABLE TRIM SHOWN FOR 1/2" :12" PITCH; LEG WILL VARY WITH ROOF PITCH CHANGES.

FLEXOSPAN	"FSS—1.5" Standing Seam Details		Finish Gable Detail
BOX 515 RAILROAD STREET SANDY LAKE. PENNSYLVANIA 16145-0515	D.UKET	ATE: 9-27-(ATE:	FSS15—11