



ERECTOR NOTES:

1. * IF "FSS-18" ROOF PANEL DOES NOT END ON A HIGH RIB THEN THE PANEL MUST BE FIELD SLIT ALLOWING FOR 2" TO BE BENT INTO A VERTICAL LEG AND USED IN CONJUNCTION WITH THE "SS-03-1" GABLE FILLER.
2. START GABLE TRIM @ EAVE & PROCEED UPWARDS CAULKING AND LAPPING EACH 4" MIN.
3. JOINTS OF INTERLOCKING TRIM TO BE STAGGERED 6" MIN.
4. "A" DIMENSION VARIES DUE TO CONSTRUCTION VARIATIONS.

FLEXOSPAN
 BOX 515 RAILROAD STREET
 SANDY LAKE, PENNSYLVANIA 16145-0515
 PHONE: 800-245-0396 ° FAX: 724-376-3864

| | | |
|-----------------------------------|---------------|----------------------------------|
| "Fss-18" Standing Segm Details | | Finish Expansion Gable Detail |
| DRAWN BY: RW | DATE: 7-13-00 | DRAWING NO. |
| CHECKED BY: CANON | DATE: | FSS18-13 |