

# Non-Load Bearing Interior Wall Framed Above Ceiling with Diagonal Kicker

## ADVANTAGES:

1. Provides good load transfer from wall to kicker.
2. Kicker does not place twisting load on wall top track.

## DISADVANTAGES:

1. Requires the wall to be framed approximately 6-8 inches above the ceiling.
2. Requires the kicker to be sized to take both compression and tension loads unless alternately kickers are used.

