


NOTES:

- 1. APPLY ON HARD SMOOTH SURFACE ONLY.
- 2. DO NOT WRAP COMPRESSION TERMINATION BAR AROUND CORNERS.
- 3. VERTICAL JOINTS IN THE PRE-CAST PANEL AS WELL AS ALL GAPS AT THE JUNCTION OF THE TILT-UP PANEL AND ROOF DECK MUST BE FULLY SEALED TO PREVENT AIR INFILTRATION.
- 4. CONTINUOUS COUNTER FLASHING REQUIRED FOR WARRANTY PROJECTS EXCEEDING 20-YEARS.



NOTE:

- 1. MEMBRANE SHOULD BE EXTENDED AT CORNERS TO PROVIDE COMPLETE COVERAGE OF THE TOP WALL SURFACE. REFER TO <u>DETAIL TPC-9.0</u>.
- 2. REFER TO <u>VERSITRIM COPING INSTALLATION INSTRUCTION</u> MANUAL FOR STEP-BY-STEP INSTRUCTION PROCEDURES.

