GEARBOSS ELITE LOCKER LAYOUT SUGGESTIONS

EXAMPLE ELEVATION VIEWS

GENERAL NOTES

Layout Suggestions (plan view labels)

- WENGER SUGGESTS 4'-0" MINIMUM CLEARANCE BETWEEN LOCKERS FACE-TO-FACE FOR ACCESSIBILITY
- WHEN ELITE LOCKERS WILL BE INSTALLED BETWEEN OBSTACLES ON BOTH SIDES, A MINIMUM 3" CLEARANCE IS REQUIRED
- 3/4" END COVER PANEL TYP. ALL EXPOSED ENDS
- TYP. VERTICAL CLOSURE PANEL OFFSET
- WENGER SUGGESTS THAT LOCKERS NOT BE PLACED WITHIN THE CLEARANCE ZONES OF SINGLE AND DOUBLE DOORS AS SHOWN
- WENGER SUGGESTS 2'-6" MINIMUM CLEARANCE FOR UNOBSTRUCTED ACCESS TO CORNER LOCKERS
- WENGER SUGGESTS 3'-0" MINIMUM CLEARANCE IN FRONT OF ALL LOCKERS FOR ACCESSIBILITY

VIEW "A" VIEW "B" VIEW "C" VIEW "D" VIEW "E"

NOTES:
1. PLACE THE PAD DRYER BLOCK ABOVE THE LOCKER ELEVATION BLOCK AS REQUIRED TO INDICATE WHICH LOCKERS ARE TO RECEIVE PAD DRYERS.

PAD DRYER BLOCK
LOCKER ELEVATION BLOCK
24"

WOOD LOCKER NOTES:

1. VERIFICATION OF BUILDING DIMENSIONS TO BE CONFIRMED BY GENERAL CONTRACTOR PRIOR TO CONSTRUCTION. PRODUCT IS PREFABRICATED IN STANDARD SIZES.
2. WALL/FLOOR AREA SPECIFIED FOR LOCKER INSTALLATION MUST BE FREE OF SURFACE MOUNTED OBSTRUCTIONS SUCH AS LIGHT SWITCHES, OUTLETS, HVAC, PIPES OR CONDUIT, WINDOW TRIM, CLOCKS, SIGNS, ETC.
3. THE LOCKER ROOMS AND STORAGE AREAS MUST AT ALL TIMES MAINTAIN A CONSISTENT CLIMATE CONTROL. THE TEMPERATURE SHOULD BE FROM 60° FAHRENHEIT (15° CELSIUS) TO 80° FAHRENHEIT (27° CELSIUS) AND THE HUMIDITY LEVEL SHOULD NOT EXCEED 60%.
4. END COVER PANELS (AT END OF LOCKER ROWS) AND CLOSURE PANELS (AT INSIDE CORNERS) TO BE SUPPLIED AS SHOWN PER DRAWING.
5. POWER SUPPLY WIRING FOR INDIVIDUAL LOCKERS INCLUDED AS SHOWN. INSTALLATION OF WALL MOUNTED JUNCTION BOXES, CONDUIT, OR MASTER SWITCHES IS NOT INCLUDED. CONNECTION OF LOCKERS TO BUILDING POWER IS NOT INCLUDED.
6. WENGER PREFERS THE LOCKER ROOM FLOOR(S) NOT BE CARPETED PRIOR TO LOCKER INSTALLATION.
7. LOCKER ROOM FLOOR(S) MUST BE CLEARED OF DEBRIS OR EQUIPMENT PRIOR TO LOCKER INSTALLATION.
8. A MINIMUM CLEARANCE OF 3" IS REQUIRED ABOVE LOCKERS FOR INSTALLATION.
9. IF THE LOCKER HAS THE PAD DRYER ACCESSORY INSTALLED, WENGER SUGGESTS 30" OF CLEARANCE BETWEEN THE TOP OF THE LOCKER AND THE CEILING/SOFFIT FOR ACCESSIBILITY.
10. UNFINISHED FLOOR, TILE OR EPOXY COATED CONCRETE FLOORING IS ACCEPTABLE PRIOR TO LOCKER INSTALLATION. ANY ADDITIONAL FLOOR COVERINGS ARE TO BE INSTALLED AFTER THE LOCKERS TO AVOID INTERFERENCE WITH THE LEGS.

PLAN VIEW

NOTES:
1. SELECT BLOCK.
2. USE ONE VISIBILITY PARAMETER (BLUE ARROW) TO SELECT THE APPROPRIATE QUANTITY.
3. USE ONE VISIBILITY PARAMETER (BLUE ARROW) TO TURN ON THE APPROPRIATE END COVER PANELS REQUIRED FOR EXPOSED ENDS.

18" | 20" | 22" | 24" | 26" | 28" | 30" | 32" | 34" | 36"

ELEVATION VIEW

NOTES:
1. SELECT BLOCK.
2. USE ONE VISIBILITY PARAMETER (BLUE ARROW) TO SELECT THE APPROPRIATE QUANTITY.
3. USE ONE VISIBILITY PARAMETER (BLUE ARROW) TO ADJUST FROM STANDARD HEIGHT TO ATTIC HEIGHT.

18" | 20" | 22" | 24" | 26" | 28" | 30" | 32" | 34" | 36"

DETAIL VIEWS

SIDE PROFILE

NOTES:
1. SELECT BLOCK, THEN USE THE VISIBILITY PARAMETER (BLUE ARROW) TO SELECT THE APPROPRIATE DETAIL.