

THE COOPER GROUP COMPUTER SIMULATION REPORT

SCOPE OF WORK

LIBERTY RESTORATION DOUBLE HUNG - NFRC 100/200/500

REPORT NUMBER

P0851.02-116-45 R0

TEST DATE

01/11/23

ISSUE DATE

01/11/23

REVISION DATE

06/07/23


PAGES

12

DOCUMENT CONTROL NUMBER

RT-R-AMER-Test-4044 (04/11/22)

©2017 INTERTEK





Total Quality. Assured.

130 Derry Court
York, Pennsylvania 17406

Telephone: 717-764-7700
Facsimile: 717-764-4129
www.intertek.com/building

TEST REPORT FOR THE COOPER GROUP

Report No: P0851.02-116-45 R0

Date: 06/07/23

REPORT ISSUED TO

THE COOPER GROUP

25 White Rock Bridge Road
Pawcatuck, Connecticut 06379

SECTION 1

SUMMARY

SERIES/MODEL: Liberty Restoration Double Hung

Architectural Testing, Inc. (an Intertek company) dba Intertek Building & Construction (B&C) was contracted to perform U-Factor, Solar Heat Gain Coefficient, Visible Transmittance and Condensation Resistance simulations in accordance with the National Fenestration Rating Council (NFRC).

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. Intertek B&C will service this report for the entire test record retention period. The test record retention period ends five years after the test date. Test records, such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained for the entire test record retention period.

FOR INTERTEK B&C:

COMPLETED BY: Jacob Points

TITLE: Simulation Technician

SIGNATURE:

DATE: 06/07/23

JP:jp

REVIEWED BY: Eric S. Leitner

TITLE: Manager - Simulations
and Thermal Testing, SIRC

SIGNATURE:

DATE: 06/07/23

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

TEST REPORT FOR THE COOPER GROUP

Report No: P0851.02-116-45 R0

Date: 06/07/23

SECTION 2

TEST METHODS

The products were evaluated in accordance with the following:

ANSI/NFRC 100-2020, Procedure for Determining Fenestration Product U-Factors

ANSI/NFRC 200-2020, Procedure for Determining Fenestration Product Solar Heat Gain Coefficient and Visible Transmittance at Normal Incidence

NFRC 500-2017, Procedure for Determining Fenestration Product Condensation Resistance Values

**Condensation Resistance results obtained from this procedure are for controlled laboratory conditions and do not include the effects of air movement through the specimen, solar radiation, and the thermal bridging that may occur due to the specific design and construction of the fenestration system opening.*

Ratings values included in this report are for submittals to an NFRC-licensed IA and are not meant to be used directly for labeling purposes. Only those values identified on a valid Certificate of Authorization (CA) by an NFRC accredited Inspection Agency (IA) are to be used for labeling purposes. The ratings values were rounded in accordance with NFRC 601, NFRC Unit and Measurement Policy.

Intertek B&C is an NFRC accredited simulation laboratory and all simulations were conducted in full compliance with NFRC approved procedures and specifications. The values included in this report are not considered in compliance with ANSI/NFRC 100, ANSI/NFRC 200, and/or NFRC 500 unless the associated validation test requirements have been satisfied, as applicable.

TEST REPORT FOR THE COOPER GROUP

Report No: P0851.02-116-45 R0

Date: 06/07/23

SECTION 3

TEST PROCEDURE

The total product, including specific frame, spacer, and glass details, was modeled using NFRC approved software.

FRAME AND EDGE MODELING	THERM 7.4.4
CENTER-OF-GLASS MODELING	WINDOW 7.4.14
TOTAL PRODUCT CALCULATIONS	WINDOW 7.4.14
SPECTRAL DATA LIBRARY	IGDB 91.0

Modeling Assumptions / Technical Interpretations

Any modeling assumptions and technical interpretations required to model this product are listed below.

- 1) To prevent air infiltration, tape was applied to all interior sash crack locations.
- 2) Generic Softwood material was used for this simulation.

SECTION 4

SIMULATION SPECIMEN DESCRIPTION

SERIES/MODEL	Liberty Restoration Double Hung
PRODUCT TYPE	Double Hung
FRAME MATERIAL	WD - Wood
SASH MATERIAL	WD - Wood
STANDARD SIZE	1200mm x 1500mm

TEST REPORT FOR THE COOPER GROUP

Report No: P0851.02-116-45 R0

Date: 06/07/23

SECTION 4 (Continued)
SIMULATION SPECIMEN DESCRIPTION

SPACER OPTIONS			
TYPE	PRIMARY SEAL	SECONDARY SEAL	CODE
TGI Spacer	PIB	Silicone	TS-D

GRID OPTIONS		
GRID SIZE	GRID TYPE	GRID PATTERN
None	-	-

REINFORCEMENT OPTIONS	
LOCATION	MATERIAL
None	-

GAS FILLING TECHNIQUE	
FILL TYPE	METHOD
90% Argon	Single probe
90% Krypton	Two-probe with concentration sensor

EDGE-OF-GLASS CONSTRUCTION	
INTERIOR CONDITION	Silicone between glazing bead and glass
EXTERIOR CONDITION	Silicone between sash leg and glass

WEATHERSTRIPPING		
TYPE	QUANTITY	LOCATION
Vinyl bulb gasket	2 rows	Bottom rail
Vinyl bulb gasket	1 row	Stiles, head
Mohair	2 rows	Head, jamb
Mohair	1 row	Sill

FRAME/SASH MATERIALS FINISH	
INTERIOR	Wood
EXTERIOR	Wood

VALIDATION MATRIX*	
PRODUCT LINE	REPORT NUMBER
None	-

*These products are part of a validation matrix. Only one is required for validation testing.

TEST REPORT FOR THE COOPER GROUP

Report No: P0851.02-116-45 R0

Date: 06/07/23

SECTION 5

SPECIALTY PRODUCTS TABLE

The specialty products method allows the manufacturer to determine the overall product SHGC and VT for any glazing option. The center of glass SHGC and/or VT must be determined using WINDOW 7.4.14. The method calculates overall product SHGC and VT indexed on center of glass properties. All values used in the calculations are truncated to six decimal place precision.

	No Dividers	Dividers < 1	Dividers > 1
SHGC0	0.003253	0.005847	0.008283
SHGC1	0.692856	0.616011	0.543846
VT0	0.000000	0.000000	0.000000
VT1	0.689603	0.610164	0.535563

$$\text{SHGC} = \text{SHGC0} + \text{SHGCc} (\text{SHGC1} - \text{SHGC0})$$

$$\text{VT} = \text{VT0} + \text{VTc} (\text{VT1} - \text{VT0})$$

TEST REPORT FOR THE COOPER GROUP

Report No: P0851.02-116-45 R0

Date: 06/07/23

SECTION 6
SIMULATION RESULTS

TOTAL PRODUCT CALCULATIONS (Liberty Restoration Double Hung)													
Option Number	Pane Thickness 1 (in)	Gap Width 1 (in)	Pane Thickness 2 (in)	Gap Width 2 (in)	Pane Thickness 3 (in)	Gap Width 3 (in)	Pane Thickness 4 (in)	Gap Fill	Low-e (Surface #)	Tint	Spacer	Grid Type	
	U-Factor (Btu/Hr-Ft2-F)			Solar Heat Gain Coefficient (SHGC) Grids (None / <1 / >=1)				Visible Transmittance (VT) Grids (None / <1 / >=1)		Condensation Resistance (CR)			
1	clr / arg / TC-88 / arg / 70/36 (#5) (DS/HM/DS) - 0.833" OD												
	0.117	0.298	0.003	0.298	0.117			ARG90	0.11(#3) / 0.105(#4) / 0.036(#5)	CL	TS-D	N	
	U-Factor		0.24	SHGC(N)				0.30	VT(N)		0.39	CR	
2	clr / kry / TC-88 / kry / 70/36 (#5) (DS/HM/DS) - 0.833" OD												
	0.117	0.298	0.003	0.298	0.117			KRY90	0.11(#3) / 0.105(#4) / 0.036(#5)	CL	TS-D	N	
	U-Factor		0.21	SHGC(N)				0.30	VT(N)		0.39	CR	
3	clr / arg / TC-88 / arg / TC-88 / arg / 70/36 (#7) (DS/HM/HM/DS) - 1.119" OD												
	0.117	0.298	0.003	0.298	0.003	0.298	0.117	ARG90	0.11(#3) / 0.105(#4) / 0.11(#5) / 0.105(#6) / 0.036(#7)	CL	TS-D	N	
	U-Factor		0.20	SHGC(N)				0.27	VT(N)		0.31	CR	
4	clr / kry / TC-88 / kry / TC-88 / kry / 70/36 (#7) (DS/HM/HM/DS) - 1.119" OD												
	0.117	0.298	0.003	0.298	0.003	0.298	0.117	KRY90	0.11(#3) / 0.105(#4) / 0.11(#5) / 0.105(#6) / 0.036(#7)	CL	TS-D	N	
	U-Factor		0.17	SHGC(N)				0.26	VT(N)		0.31	CR	
5	clr / arg / SC-75 / arg / 70/36 (#5) (DS/HM/DS) - 0.833" OD												
	0.117	0.298	0.003	0.298	0.117			ARG90	0.76(#3) / 0.045(#4) / 0.036(#5)	CL	TS-D	N	
	U-Factor		0.27	SHGC(N)				0.24	VT(N)		0.37	CR	
6	clr / kry / SC-75 / kry / 70/36 (#5) (DS/HM/DS) - 0.833" OD												
	0.117	0.298	0.003	0.298	0.117			KRY90	0.76(#3) / 0.045(#4) / 0.036(#5)	CL	TS-D	N	
	U-Factor		0.23	SHGC(N)				0.24	VT(N)		0.37	CR	
7	clr / arg / SC-75 / arg / SC-75 / arg / 70/36 (#7) (DS/HM/HM/DS) - 1.119" OD												
	0.117	0.298	0.003	0.298	0.003	0.298	0.117	ARG90	0.76(#3) / 0.045(#4) / 0.76(#5) / 0.045(#6) / 0.036(#7)	CL	TS-D	N	
	U-Factor		0.21	SHGC(N)				0.19	VT(N)		0.29	CR	
8	clr / kry / SC-75 / kry / SC-75 / kry / 70/36 (#7) (DS/HM/HM/DS) - 1.119" OD												
	0.117	0.298	0.003	0.298	0.003	0.298	0.117	KRY90	0.76(#3) / 0.045(#4) / 0.76(#5) / 0.045(#6) / 0.036(#7)	CL	TS-D	N	
	U-Factor		0.18	SHGC(N)				0.19	VT(N)		0.29	CR	
9	lami 060PVB / arg / TC-88 / arg / 70/36 (#5) (LAMI/HM/DS) - 1.014" OD												
	0.294	0.298	0.003	0.298	0.117			ARG90	0.11(#3) / 0.105(#4) / 0.036(#5)	CL	TS-D	N	
	U-Factor		0.24	SHGC(N)				0.29	VT(N)		0.38	CR	
10	lami 060PVB / kry / TC-88 / kry / 70/36 (#5) (LAMI/HM/DS) - 1.014" OD												
	0.294	0.298	0.003	0.298	0.117			KRY90	0.11(#3) / 0.105(#4) / 0.036(#5)	CL	TS-D	N	
	U-Factor		0.20	SHGC(N)				0.28	VT(N)		0.38	CR	

TEST REPORT FOR THE COOPER GROUP

Report No: P0851.02-116-45 R0

Date: 06/07/23

SECTION 6 (Continued)
SIMULATION RESULTS

TOTAL PRODUCT CALCULATIONS (Liberty Restoration Double Hung)													
Option Number	Pane Thickness 1 (in)	Gap Width 1 (in)	Pane Thickness 2 (in)	Gap Width 2 (in)	Pane Thickness 3 (in)	Gap Width 3 (in)	Pane Thickness 4 (in)	Gap Fill	Low-e (Surface #)	Tint	Spacer	Grid Type	
	U-Factor (Btu/Hr-Ft2-F)			Solar Heat Gain Coefficient (SHGC) Grids (None / <1 / >=1)				Visible Transmittance (VT) Grids (None / <1 / >=1)			Condensation Resistance (CR)		
11	lami 060PVB / arg / TC-88 / arg / TC-88 / arg / 70/36 (#7) (LAMI/HM/HM/DS) - 1.267" OD												
	0.294	0.298	0.003	0.298	0.003	0.298	0.117	ARG90	0.11(#3) / 0.105(#4) / 0.11(#5) / 0.105(#6) / 0.036(#7)	CL	TS-D	N	
	U-Factor 0.20			SHGC(N) 0.25				VT(N) 0.31			CR 70		
12	lami 060PVB / kry / TC-88 / kry / TC-88 / kry / 70/36 (#7) (LAMI/HM/HM/DS) - 1.267" OD												
	0.294	0.298	0.003	0.298	0.003	0.298	0.117	KRY90	0.11(#3) / 0.105(#4) / 0.11(#5) / 0.105(#6) / 0.036(#7)	CL	TS-D	N	
	U-Factor 0.17			SHGC(N) 0.25				VT(N) 0.31			CR 70		
13	lami 090SGP / arg / TC-88 / arg / 70/36 (#5) (LAMI/HM/DS) - 1.052" OD												
	0.324	0.298	0.003	0.298	0.117			ARG90	0.11(#3) / 0.105(#4) / 0.036(#5)	CL	TS-D	N	
	U-Factor 0.24			SHGC(N) 0.28				VT(N) 0.37			CR 63		
14	lami 090SGP / kry / TC-88 / kry / 70/36 (#5) (LAMI/HM/DS) - 1.052" OD												
	0.324	0.298	0.003	0.298	0.117			KRY90	0.11(#3) / 0.105(#4) / 0.036(#5)	CL	TS-D	N	
	U-Factor 0.20			SHGC(N) 0.27				VT(N) 0.37			CR 67		
15	lami 090SGP / arg / TC-88 / arg / TC-88 / arg / 70/36 (#7) (LAMI/HM/HM/DS) - 1.349" OD												
	0.324	0.298	0.003	0.298	0.003	0.298	0.117	ARG90	0.11(#3) / 0.105(#4) / 0.11(#5) / 0.105(#6) / 0.036(#7)	CL	TS-D	N	
	U-Factor 0.20			SHGC(N) 0.24				VT(N) 0.30			CR 70		
16	lami 090SGP / kry / TC-88 / kry / TC-88 / kry / 70/36 (#7) (LAMI/HM/HM/DS) - 1.349" OD												
	0.324	0.298	0.003	0.298	0.003	0.298	0.117	KRY90	0.11(#3) / 0.105(#4) / 0.11(#5) / 0.105(#6) / 0.036(#7)	CL	TS-D	N	
	U-Factor 0.17			SHGC(N) 0.24				VT(N) 0.30			CR 70		
17	clr / arg / 70/36 (#3) (DS/DS) - 0.534" OD												
	0.117	0.298	0.117					ARG90		CL	TS-D	N	
	U-Factor 0.33			SHGC(N) 0.33				VT(N) 0.48			CR 52		
18	clr / kry / 70/36 (#3) (DS/DS) - 0.534" OD												
	0.117	0.300	0.117					KRY90	0.036(#3)	CL	TS-D	N	
	U-Factor 0.28			SHGC(N) 0.34				VT(N) 0.48			CR 56		
19	clr / air / 70/36 (#3) (DS/DS) - 0.534" OD												
	0.117	0.300	0.117					AIR	0.036(#3)	CL	TS-D	N	
	U-Factor 0.37			SHGC(N) 0.33				VT(N) 0.48			CR 48		
20	clr / arg / 80/71 (#3) (DS/DS) - 0.534" OD												
	0.117	0.300	0.117					ARG90	0.082(#4)	CL	TS-D	N	
	U-Factor 0.36			SHGC(N) 0.47				VT(N) 0.55			CR 29		

TEST REPORT FOR THE COOPER GROUP

Report No: P0851.02-116-45 R0

Date: 06/07/23

SECTION 6 (Continued)
SIMULATION RESULTS

TOTAL PRODUCT CALCULATIONS (Liberty Restoration Double Hung)												
Option Number	Pane Thickness 1 (in)	Gap Width 1 (in)	Pane Thickness 2 (in)	Gap Width 2 (in)	Pane Thickness 3 (in)	Gap Width 3 (in)	Pane Thickness 4 (in)	Gap Fill	Low-e (Surface #)	Tint	Spacer	Grid Type
	U-Factor (Btu/Hr-Ft2-F)			Solar Heat Gain Coefficient (SHGC) Grids (None / <1 / >=1)				Visible Transmittance (VT) Grids (None / <1 / >=1)		Condensation Resistance (CR)		
21	clr / kry / 80/71 (#3) (DS/DS) - 0.534" OD											
	0.117	0.300	0.117					KRY90	0.082(#4)	CL	TS-D	N
	U-Factor 0.34			SHGC(N) 0.47				VT(N) 0.55		CR 32		
22	clr / air / 80/71 (#3) (DS/DS) - 0.534" OD											
	0.117	0.300	0.117					AIR	0.082(#4)	CL	TS-D	N
	U-Factor 0.37			SHGC(N) 0.47				VT(N) 0.55		CR 27		
23	lami 060PVB / arg / 70/36 (#3) (LAMI/DS) - 0.714" OD											
	0.294	0.300	0.117					ARG90	0.036(#3)	CL	TS-D	N
	U-Factor 0.32			SHGC(N) 0.32				VT(N) 0.47		CR 53		
24	lami 060PVB / kry / 70/36 (#3) (LAMI/DS) - 0.714" OD											
	0.294	0.300	0.117					KRY90	0.036(#3)	CL	TS-D	N
	U-Factor 0.27			SHGC(N) 0.32				VT(N) 0.47		CR 56		
25	lami 060PVB / air / 70/36 (#3) (LAMI/DS) - 0.714" OD											
	0.294	0.300	0.117					AIR	0.036(#3)	CL	TS-D	N
	U-Factor 0.37			SHGC(N) 0.32				VT(N) 0.47		CR 49		
26	lami 090SGP / arg / 70/36 (#3) (LAMI/DS) - 0.714" OD											
	0.324	0.300	0.117					ARG90	0.036(#3)	CL	TS-D	N
	U-Factor 0.32			SHGC(N) 0.31				VT(N) 0.46		CR 53		
27	lami 090SGP / kry / 70/36 (#3) (LAMI/DS) - 0.714" OD											
	0.324	0.300	0.117					KRY90	0.036(#3)	CL	TS-D	N
	U-Factor 0.27			SHGC(N) 0.31				VT(N) 0.46		CR 57		
28	lami 090SGP / air / 70/36 (#3) (LAMI/DS) - 0.714" OD											
	0.324	0.300	0.117					AIR	0.036(#3)	CL	TS-D	N
	U-Factor 0.36			SHGC(N) 0.31				VT(N) 0.46		CR 49		
29	lami 060PVB / arg / lami 060PVB (#3) (LAMI/LAMI) - 0.895" OD											
	0.294	0.300	0.294					ARG90		CL	TS-D	N
	U-Factor 0.43			SHGC(N) 0.47				VT(N) 0.55		CR 44		
30	lami 090SGP / arg / lami 090SGP (#3) (LAMI/LAMI) - 0.948" OD											
	0.324	0.300	0.324					ARG90		CL	TS-D	N
	U-Factor 0.43			SHGC(N) 0.44				VT(N) 0.51		CR 44		



Total Quality. Assured.

130 Derry Court
York, Pennsylvania 17406

Telephone: 717-764-7700
Facsimile: 717-764-4129
www.intertek.com/building

TEST REPORT FOR THE COOPER GROUP





Report No: P0851.02-116-45 R0

Date: 06/07/23

SECTION 7


DRAWINGS / BILL OF MATERIALS

The drawings which follow have been reviewed by Intertek B&C and are representative of the simulation results reported herein. Any deviations are documented herein or on the drawings.



APPROVED BY:

SIGNATURE DATE



DRAWINGS PROVIDED BY:

The Cooper Group LLC

25 White Rock Road Pawcatuck, CT 06379
Phone: 860-599-2481 Fax: 860-599-1071
www.thecoopergroupct.com

DISCLAIMER

THESE DRAWINGS ARE DESIGNED IN ACCORDANCE WITH AN ACCEPTABLE STANDARD OF CARE AND ARE AN ACCURATE PORTRAYAL OF STANDARD CONSTRUCTION METHODS. WHILE THE PLANS WERE DESIGNED FOR GENERAL CONSTRUCTION, INDIVIDUAL STATE AND/OR LOCAL AUTHORITIES MAY REQUIRE MODIFICATIONS DUE TO MORE STRINGENT LOCAL REGULATIONS. GENERAL CONTRACTOR, WITH THE CLIENT/OWNER, TO REVIEW PLANS AND ENSURE THAT THE SET CONFORMS TO ALL SUCH RESTRICTIONS IN THE MUNICIPALITY IN WHICH THE PROJECT IS LOCATED. THE CLIENT/GENERAL CONTRACTOR IS RESPONSIBLE FOR THE VERIFICATION OF ALL MUNICIPAL REGULATIONS. THE COOPER GROUP DESIGN IS NOT RESPONSIBLE FOR ANY MISUSE AND/OR MISHAPS BEFORE, DURING, OR AFTER THE USE OF THESE DRAWINGS FOR CONSTRUCTION.

DISCLAIMER

THESE DRAWINGS & SPECIFICATIONS ARE THE PROPERTY OF THE COOPER GROUP AND SHALL NOT BE REPRODUCED, COPIED, OR USED AS THE BASIS FOR MANUFACTURING OR SALES WITHOUT THE PERMISSION OF THE COOPER GROUP

PHASE:
NOT FOR CONSTRUCTION

MARK	DATE	DESCRIPTION

PROJECT NUMBER: NFRC TESTING

DRAWN BY: JRG --/--

CHECKED BY:

DATE: 8/2/22

SCALE: NONE AS NOTED

GATEWAY WINDOW DRAWINGS FOR AAMA



Total Quality. Assured.

130 Derry Court
York, Pennsylvania 17406

Telephone: 717-764-7700
Facsimile: 717-764-4129
www.intertek.com/building

TEST REPORT FOR THE COOPER GROUP

Report No: P0851.02-116-45 R0

Date: 06/07/23

SECTION 8

REVISION LOG

REVISION #	DATE	PAGES	REVISION
.01 R0	01/11/23	N/A	Original report issue.
.02 R0	06/07/23	All	Added options #17-30