

TEST REPORT

100 Clemson Research Blvd. Anderson, SC 29625 (864) 656-1094 Fax: (864) 656-1095 www.brickandtile.org



Results of Tests on brick Conducted in accordance with C67/C67M - 23a Standard Test Methods for Sampling and Testing Brick and Structural Clay Tile

02/16/2024

Name: Palmetto Brick Company

P. O. Box 430

Cheraw, SC 29520-0430

Phone: 843-320-1137

Fax: 843-537-4802 Report Number: 12439-30858

Description: Rose Body

Plant: Palmetto Brick Company

1/31/2024

Sampled Date: 1/31/2024 Received Date: 1/31/2024

Fired Date: Product Code:

Lot Number:

Absorption	1		2		3		4		5		Average	Test Date
24 Hour Cold Water (%)	6.1		6.1		6.0		6.1		6.0		6.1	2/7/2024
5 Hour Boiling Water (%)	7.	9	7.8		7.7		7.9		7.8		7.8	
Saturation Coefficient	0.78		0.77		0.78		0.77		0.77		0.77	
Compressive Strength	1		2		3		4		5		Average	Test Date
psi	13,460		11,170		14,590		13,110		12,000		12,870	2/8/2024
IRA (Oven Dried Method)	6		7		8		9		10		Average	Test Date
g/min/30 in. ²	17.2		17.4		17.1		17.2		17.7		17.3	2/6/2024
Efflorescence	11		12		13		14		15			Test Date
Efflorescence Detection	Not Effloresced			2/15/2024								
Void Area	1	2	3	4	5	6	7	8	9	10	Average	Test Date
Void Area (%)	24	24	24	24	24	24	25	24	24	24	24	2/6/2024

The brick represented by the test results shown here comply with the physical property requirements of the standards listed below:

ASTM C216 - 23 Standard Specification for Facing Brick (Solid Masonry Units Made From Clay or Shale) Grade: SW, MW

Katherine Hill, Quality Manager

Lab Reference: 12439.30858 Page 1 of 1